

JRH Consulting Engineers + Architects

3555 Veterans Memorial Highway Suite A, Ronkonkoma New York 11779

Tel: (631) 234-2220 Fax: (631) 234-2221 e-mail: info@holzmacher.com

Sewage Treatment Plant Improvements

Bid #VOG2026 – Contract No. 1 Screw Pump Replacement

INC. VILLAGE OF GREENPORT
SUFFOLK COUNTY, NEW YORK

ADDENDUM - 1

Date: March 16, 2026

Following are questions received by our office from potential bidders regarding the above project. For convenience we have restated the bidders' questions below followed by responses in *italics*:

1. What are the permitted working hours? Will overtime be permitted?

Contractors are expected to work between the hours of 7am – 4pm Monday through Friday, unless otherwise approved by the Village. Overtime will be approved on a case-by-case basis and at the discretion of the Village.

2. The walkthrough indicated the corrugated metal covers should be replaced, but Section 432441 – OPEN SCREW PUMPS 1.3.E says to reuse existing fiberglass trough cover panels. Which type of cover is required? Would this be added to the bid?

Village of Greenport will supply replacement trough covers to the Contractor. Contractor will be responsible for installing the new trough covers in-kind. The two (2) replacement trough covers shall be constructed of Fiberglass, are 21.5' x 3.5' in size. Item #5 has been added to the Bidder Price Sheet # PB-2 outlining the scope change, and has been attached to this Addenda.

3. During the walkthrough the facility mentioned adding heat trace to the influent area to prevent freezing issues experienced during this winter. Where would that be installed? What type and power is required? What electrical service would that be wired to? Is this something that will be added to the bid?

Installation of heat trace and/or heating elements related to the screw pump basin is not included in this scope.

4. Will existing motor starter and electrical controls be re-utilized?

Existing motor starter and electrical controls will be re-utilized. If, during the course of the project, replacement is required, a change order will be issued for their replacement.

5. Can existing motor mounts be reused, or will new anchors be required for installation?

The existing motor mounts will be reused. If, during the course of the installation, the mounts are found to be insufficient, a change order will be issued for their replacement.

6. Can the existing grease transference piping be reused or will the existing pipe need to be removed from concrete and replaced in kind?

All existing grease piping will be required to be removed and replaced including pipe embedded in the screw pump channel. Grease transference piping will be installed as recommended by the manufacturer.

ITEM 1 – Existing East Pump Removal

Including in general, furnishing of labor, crane, tools, equipment and all associated appurtenances necessary to prepare the east clarifier and to remove the existing east screw pump and to make the site ready for installation work, to facilitate a complete installation.

LUMP SUM _____ (\$ _____)
DOLLARS

ITEM 2 – New East Pump Installation

Including in general, installation of new east screw pump, furnished by Owner, and furnishing of all labor, crane, fittings, tools, equipment, with start-up, testing and all associated appurtenances necessary for a complete installation.

LUMP SUM _____ (\$ _____)
DOLLARS

ITEM 3 – Existing West Pump Removal

Including in general, furnishing of labor, crane, tools, equipment and all associated appurtenances necessary to prepare the east clarifier and to remove the existing west screw pump and to make the site ready for installation work, to facilitate a complete installation.

LUMP SUM _____ (\$ _____)
DOLLARS

ITEM 4 – New West Pump Installation

Including in general, installation of new west screw pump, furnished by Owner, and furnishing of all labor, crane, fittings, tools, equipment, with start-up, testing and all associated appurtenances necessary for a complete installation.

LUMP SUM _____ (\$ _____)
DOLLARS

INC. VILLAGE OF GREENPORT
SEWAGE TREATMENT PLANT IMPROVEMENTS
Contract No. 1 – Screw Pump Replacement
BID DATE: Friday March 20, 2026

ITEM 5 – Installation of New Trough Cover Panels (East and West)

Including in general, Removal and Replacement of the existing tough covers in kind. Replacement Trough Covers shall be furnished by Owner. Includes furnishing of all labor, crane, hardware, tools, equipment and all associated appurtenances necessary for a complete installation.

LUMP SUM _____ (\$ _____)
DOLLARS

TOTAL BID (SUM OF ITEMS 1, 2, 3, 4 & 5)

_____ (\$ _____)
DOLLARS

INC. VILLAGE OF GREENPORT
SEWAGE TREATMENT PLANT IMPROVEMENTS
Contract No. 1 – Screw Pump Replacement
BID DATE: Friday March 20, 2026

FAILURE OF THE CONTRACTOR TO COMPLETE ALL WORK WITHIN THE SPECIFIED TIME PERIODS WILL SUBJECT HIM TO LIQUIDATED DAMAGES AS SET FORTH IN THE CONTRACT, IN THE SUM OF FIVE HUNDRED DOLLARS (\$500.00) PER DAY, COMMENCING WITH THE RESPECTIVE DATE ESTABLISHED FROM THE NOTICE TO PROCEED.

WITHIN TEN (10) CONSECUTIVE CALENDAR DAYS AFTER THE DATE OF THE NOTICE OF AWARD, THE BIDDER SHALL EXECUTE THE CONTRACT AND FURNISH THE REQUIRED PERFORMANCE BOND AND INSURANCES.

THE BOARD OF TRUSTEES RESERVES THE RIGHT TO AWARD THIS CONTRACT OR TO REJECT ANY OR ALL BIDS.

THE BIDDER REPRESENTS HERewith THAT HE IS AWARE OF THE WORKING CONDITIONS, HAS CAREFULLY REVIEWED THE PROPOSAL AND SPECIFICATION, HAS CHECKED AND CERTIFIES THE ACCURACY OF THE BID.

THE UNDERSIGNED HEREBY ACKNOWLEDGE RECEIPT OF THE FOLLOWING ADDENDA, IF ANY.

ADDENDUM

DATED

“Each bidder on a public work contract in Nassau, Suffolk or Westchester Counties, where the entire cost of such public work is under one million five hundred thousand dollars, shall submit with its bid a separate sealed list that names each subcontractor that the bidder will use to perform work on the contract, and the agreed-upon amount to be paid to each, for: a) plumbing and gas fitting, b) steam heating, hot water heating, ventilating and air conditioning apparatus and c) electric wiring and standard illuminating fixtures.”

INC. VILLAGE OF GREENPORT
SEWAGE TREATMENT PLANT IMPROVEMENTS
Contract No. 1 – Screw Pump Replacement
BID DATE: Friday March 20, 2026

THE UNDERSIGNED HEREBY INDICATES THAT IT HAS ENCLOSED A SEALED LIST OF SUBCONTRACTORS FOR THE FOLLOWING TRADES:

- A) Plumbing and Gas Fitting _____Yes _____No
- B) Heating, Ventilation and Air Conditioning _____Yes _____No
- C) Electric Wiring and Standard Illuminating Fixtures _____Yes _____No

BIDDER: _____

BIDDER'S ADDRESS: _____

SIGNED BY: _____ TITLE _____

DATE: _____

FEDERAL NO. OR
SOCIAL SECURITY NO.: _____

TELEPHONE NUMBER WHERE THE CONTRACTOR OR A COMPETENT REPRESENTATIVE CAN ACCEPT A TELEPHONE MESSAGE AND PROVIDE A REASONABLE REPLY AS SOON AS POSSIBLE, BUT NOT LATER THAN 24 HOURS.

INC. VILLAGE OF GREENPORT
SEWAGE TREATMENT PLANT IMPROVEMENTS
Contract No. 1 – Screw Pump Replacement
BID DATE: Friday March 20, 2026

NO TEXT THIS PAGE